

Works to be quote for on Ludlow Town Council land

<b>Tree ref</b>	<b>Species</b>	<b>Site</b>	<b>Task</b>	<b>Priority</b>	<b>Conservation Area status</b>
2020/0105	Common alder	Linney riverside park	Remove all major deadwood (>80mm dia) & stubs from throughout crown.	3 months	Yes Ludlow
2020/0106	Common alder	Linney riverside park	Remove all major deadwood (>80mm dia) & stubs from throughout crown, including the hanging branch.	3 months	Yes Ludlow
2020/0022	Common hawthorn	Henley Road cemetery	Fell to ground level	6 months	No
2020/0046	Silver maple	Lower Corve St garden	Crown reduce to clear building by approx 2m. Pruning cuts should be <100mm in diameter	6 months	Yes Ludlow
2020/0049	English Yew	St Laurence's Garden of Rest	Crown lift branch tips to 2.5m all round, crown reduce to clear building by 2m. Cut diameter should be <75mm.	6 months	Yes Ludlow
2020/0078	False acacia	Castle Gardens	Remove all major deadwood (>80mm dia) & stubs from throughout crown	6 months	Yes Ludlow
2020/0094	Honey locust	St Johns Gardens	Crown reduce southern canopy by 2-3m to create les end weight on the crown.	6 months	Yes Ludlow
2020/0102	Sycamore	Linney riverside park	Crown reduce tree height to 20cm above previous topping points. Retain all live branch growth below this height. Shorten the length of all branches longer than 2m, by approx 50% to reshape crown. Apply all woodchip arising around the base of the tree to a depth of 75mm, do not pile against the tree base.	6 months	Yes Ludlow
2020/0115	Common alder	Linney riverside park	Repollard back to stump at approx 1m.	6 months	Yes Ludlow